別添4/Attachment4

原状回復における仕様詳細/Specification details in reinstatement

| Detail | Terms and Conditions to reinstate the returned space (230 sq.m.) |
|------------------------|---|
| Ceiling/T-Bar | Specification of ceiling shall be "OWA Acoustic Futura 60 Premium" |
| | size (WxLxT)=600x1200x15mm. (4-sided edge closure) |
| Wall Paint | Specification of wall paint shall be white color, |
| | color no. ″TOA Dura clean D100″ |
| Vinyl Tile | Specification of vinyl tile shall be "DYNOFLEX, colorD-15, size (WxLxT)=300x300x2.5 (or2)mm." |
| | with rubber floor/skirt covering. After finishing the tile flooring, wax the floor 3times. |
| Rubber Sheet | After finishing the tile flooring, rubber sheet shall be covered around the edge of the tile. |
| | Color of rubber sheet is black color. |
| Smoke Detector | It shall be the building's responsibility to install Smoke Detector. |
| Heat Detector | Specification of heat detector is "5600 series" |
| | System Sensor |
| | Model: No.5601P |
| | Single Circuit 135°F(57°C) (Rate of Rise Fixed Temp.) |
| Lighting / Lamp | All lamps must have a reverse channel for air to return |
| Curtain Rail | Curtain and its rails shall be removed. Repaint the color as same as current color |
| | which is oil color. |
| Door | Double Transparent Temper Glass Doors for the returned space (230 sq.m.) |
| | size 200x180cm, thickness 12mm. Shock absorber, stainless steell handles : Long around 350mm. |
| Wall Plug | Remove all plugs except the plugs at the column |
| Floor Plug | Not allow to install the floor plug. Floor plug should be removed. |
| Speaker use for | No should be assessed |
| Announcement | should be removed. |
| Air Supply | Air supply should be grill air, size 1x1 ft., silver color, |
| | Measure the ventilation speed of each air grill, it should be according to the building's standard. |
| Telephone Plug | The telephone plugs and telephone line have to be removed all the way from the inside of |
| | returned lease space to the end in the shaft room which is beside the passenger lift, in front of the library room. |
| | Individual electricity meter and Load center should be installed inside of the returned leased space separately |
| Individual Electricity | and The Japan Foundation shall be responsible for the installation cost. |
| Meter&Load Center | Note: The electricity system for the returned space shall be separated completely, |
| | not involve with electricity system of the other existing area and the common area in front of the returned space. |